

Historic, Archive Document

Do not assume content reflects current scientific knowledge, policies, or practices.

aSB379
.C5U5

(*)
1500

Red Tart Cherry Site Inventory




FOR
LEELANAU COUNTY
MICHIGAN

AL-33 Bookplate
(1-63)

NATIONAL

**A
G
R
I
C
U
L
T
U
R
A
L**



LIBRARY

U. S. DEPT. OF AGRICULTURE
NATIONAL
APR 17 1975
CALIFORNIA - FREE

CONTENTS

A FRUIT SITE INVENTORY	i
Objective	i
RED TART CHERRY SITE INVENTORY	1
Site Requirements for Red Tart Cherries	1
Soil Factors	1
Physiographic Factors	2
Climatic Factors	2
FRUIT SITE RATING SHEETS	3 & 4
Map Preparation	5
Explanation of Colors	5 & 6
Interpretation of the Map	7
Modification of Hazards	7
HOW TO USE THE RED TART CHERRY SITE INVENTORY	8
Locating Areas	8
Finding Information	8
APPENDIX	9, 10, & 11
REFERENCE MATERIAL	12
INDEX TO MAP SHEETS	13
LEGEND	14

CHERRY SITE MAPS

3

A FRUIT SITE INVENTORY

A method of identifying and mapping red tart cherry sites was developed in Northwestern Michigan. The basic procedure described here for cherry sites can be adapted to other geographic areas and for other fruit crops with exacting requirements of soil, topography, and climate.

Objective

The objective of the red tart cherry site inventory is to evaluate a parcel of land in a given location according to its capability to consistently produce cherry crops. Such an inventory is valuable for determining the location, extent, and quality of available red tart cherry sites.

Areas with the favorable combination of soil and climate for producing red tart cherries are located and evaluated. This type of information is useful in many ways, one of which is protecting these rather limited areas from being despoiled by the pressures for other land uses.

Dependable red tart cherry sites are in demand for other uses. Generally high-lying, they are choice locations for home building. Community planners need to recognize the value of these relatively scarce sites, to set priorities on their use and to give protection, if necessary, to the environmental condition that makes these sites productive. Construction of a building complex or even the raised roadbed of a new highway built across a major air flowageway may change a good, frost-protected site to one that is unsatisfactory for production of red tart cherries.

The site inventory also may help prevent the planting of orchards on unfavorable sites. The grower, the processing industry, and the community suffer as a result of fruit planted on marginal sites. The red tart cherry industry illustrates this problem. It has had a history of feast and famine for many years. The years of high production have usually resulted in low prices. Low production years resulted in higher prices. Generally, the high price years encouraged growers to plant new orchards, many on marginal sites. When these trees come into production, those on marginal sites bear only in years of favorable weather conditions. This increases the already fluctuating production - high in years of favorable weather, very low in others.

Processors and market outlets are dependent on a stable supply of cherries. The cherry processor cannot maintain plant capacity to handle peak production that occurs only 2 or 3 years out of 10. When the market is glutted, prices drop to a level where neither grower nor processor can operate at a profit. In years of low production, only the favorable sites produce a good crop of cherries. Some growers have nothing to sell and the processor has equipment standing idle. The industry is always faced with the problem of furnishing a uniform annual supply in order to attract the consumer to purchase cherries and not a substitute fruit. It is difficult for an industry to maintain its position in the market place with such wide variations in production, caused in part by orchards planted on marginal sites.

A rating system has been developed as a way to inventory red tart cherry sites in order to meet the needs of the growers, processors, community planners, and others.

Inventory's information can:

1. Assist the potential fruit grower in selecting a site for a profitable enterprise.
2. Assist the present fruit grower in reassessing present orchards and in planning future plantings.
3. Assist growers in relocating in a more favorable location or in obtaining a larger economic unit.

Other Uses:

1. Agriculture assessment - to delineate lands that should receive tax consideration if they are to be maintained in agricultural use.
2. Zoning commissions - to delineate potential fruit sites and plan for nonconflicting uses adjacent to fruit areas.
3. Planners of community services - to cause the least amount of fragmentation of ownership.
4. Comprehensive areawide planners - to establish basis for a stable industry.
5. Investors - to evaluate risks in capital investments pointed toward developing fruit-producing areas with a favorable and stable base.
6. Tourists - fruit production increases and enhances the tourism and recreational potential of an areas. Tourists are a by-product of the total fruit industry.

Agencies or groups that might use a fruit site inventory include:

1. Processing groups
2. Banks or credit organizations
3. Nurseries
4. Irrigation and other equipment suppliers
5. Fruit specialists
6. Agricultural research groups
7. Climatologists
8. Resort and recreation groups
9. Zoning and planning boards
10. Real estate sales organizations

RED TART CHERRY SITE INVENTORY
Leelanau County, Michigan

Field work by: Keith R. Martell, Marvin Hansen, Roscoe Barber, Richard Larson, and Guy Springer (all of the Soil Conservation Service) and T. Michael Thomas, County Extension Director, Leelanau County.

Leelanau County is in the northwestern part of the lower peninsula of Michigan (fig. 1). It has a total area of about 349 square miles or 223,330 acres. In 1970, the county had a population of 10,864. Leland, on the shore of Lake Michigan, is the county seat and the access point to the Fox and Manitou Islands. Leland is 235 miles northwest of Detroit, 150 miles north of Grand Rapids, 175 miles north-northwest of Lansing, and 110 miles south-southwest of the Straits of Mackinac.



Figure 1 - Location of Leelanau County

Site Requirements for Red Tart Cherries

The Leelanau County inventory was based on the site requirements of the Montmorency red tart cherry. This fruit occupies the most acreage and is economically the most important agricultural crop to the county.

Following are factors which make a desirable red tart cherry site in Leelanau County:

Soil Factors

The most desirable soil is a well drained, sandy loam that is well aerated and has a medium to high natural fertility. The soil must have a moderate available water capacity, a moderate to moderately rapid permeability, and at least 48 inches of depth to permit unrestricted root penetration for good growth and anchorage. Soils having these characteristics will usually respond well to the proper management techniques for growing red tart cherries.

Physiographic Factors

Physiographic features of the site determine to a large extent the microclimate, which in turn influences yield of cherries. Differences of soil, soil cover, elevation, and exposure are responsible for microclimatic variations that are extremely important. The most desirable site would be one on which all effects of local climate are favorable for best production. Slope gradient should be 2 to 12% to permit ease of equipment use and other soil management practices, yet still provide adequate air drainage. Slope should be fairly uniform with well-defined water and air flowageways. There should be no constriction or obstruction to the cold air flowageways. The site should be located so that cold air from adjacent land does not drain over or onto it. Also, it is more desirable to have air drained into a cold air storage basin over water than into a cold air storage basin over land. Orchards should be planted above the principal spring freeze line ^{1/} of the cold air storage basin. Finally, the general exposure should permit the crop to take full advantage of sunshine yet not be exposed to damaging winds during pollination and fruit bearing.

Climatic Factors

The spring temperature should remain cool to retard fruit bud development and minimize danger of damage due to spring freezes. During the pollination-fertilization period of bloom, temperatures should exceed 50° F in daytime for bee activity and should not drop below 28 to 30° F for any period of time. The site should be as free of fog as possible. Warm sunny days without desiccating winds are important for good pollination and fruit set.

The lowest winter temperatures seldom, if ever, should get as low as -15 to -20° F for tart cherries. An insulating cover of snow can provide for uniform soil temperature, but whether or not this is a significant factor in fruit production is not known. (Sunshine reflected from the snow cover may cause wide and rapid variations of temperature in tree trunks, resulting in tree damage which leads to reduced production. Management techniques can control this problem.)

The factors and weights given them for red tart cherry sites are shown on the Fruit Site Rating Sheet.

^{1/} See Appendix for definition

FRUIT SITE RATING SHEET

I. Soil Factors

	<u>Rating Value</u>	<u>Actual Score</u>
A. Texture: 1/ Possible Score = (40)		
(Sands)	10	
Sandy (Loamy Sands)	20	
Coarse loamy	40	
Fine loamy	30	
Clayey	10	
Clayey (very fine)	5	
Organic	0	
B. Drainage: Possible Score = (40)		
Well drained	40	
Moderately well drained	30	
Somewhat poorly drained	20	
Poorly and very poorly drained	10	
C. Restrictions to Rooting: Possible Score = (20)		
No restrictions to 48 inches	20	
Coarse fragments within 48 inches	10	
Pans within 48 inches	5	
(Total possible score = 100)		I. Total Actual Score _____

II. Physiographic Factors

A. Slope: Possible Score = (35)		
2-12%	35	
0-2%	30	
12-18%	15	
Over 18% (Unsuitable for mechanical harvest)	10	
B. Elevation above Principal Spring Freeze Line: Possible Score = (30)		
100 feet +	30	
50-100 feet	25	
20-50 feet	20	
Less than 20 feet	0	
C. Air Drainage: Possible Score = (35)		
Uninterrupted airflow to major air storage basin	35	
Minor obstruction to air flow to major air storage basin	25	
Major obstruction to air flow to air storage basin	5	
(Total possible score = 100)		II. Total Actual Score _____

1/ Refers to soil family texture as used in the Soil Classification System of the National Cooperative Soil Survey.

FRUIT SITE RATING SHEET (cont'd)

III. Climatic Factors

	<u>Rating Value</u>	<u>Actual Score</u>
A. <u>Spring Temperatures: Possible Score = (70)</u> Probability of damaging freeze or cold weather during fruit set during 10-year period.		
(2 in 10)	70	
(3-4 in 10)	40	
(5-6 in 10)	10	
B. <u>Winter Temperatures: Possible Score = (30)</u> Probability of extreme cold winter temperature during 10-year period.		
(2 in 10)	30	
(3-4 in 10)	5	
(5-6 in 10)	0	

(Total possible score = 100)

III. Total Actual Score _____

(The occurrence of fog, wind, and hail were not given individual ratings, however, they were included in the overall site evaluation.)

Summary of Scores - Section I _____
 " II _____
 " III _____

Site Rating or Total Score _____

Interpretation of Fruit Site Ratings

<u>Total Score</u>	<u>Map Color</u>	<u>Difficulty of Overcoming Limitations to Production</u>
300-290	Green	Slight
285-225	Yellow	Moderate
220-170	Red	Severe
165 or less	No Color	Very Severe

Following onsite examination and scoring of each item in the rating sheet, the total score for a site is obtained by adding the sums of the rating scores for the soil, physiographic, and climatic factors. This total is referred to as Fruit Site Rating.

Map Preparation

Colors and symbols are used to identify and to delineate fruit sites. The ranges (interval) of fruit site ratings used in the red tart cherry site inventory in Leelanau County are shown with map colors and degree of limitation on the bottom of the Fruit Site Rating Sheet.

Explanation of Colors

GREEN

The areas colored green on the map are within the narrow range of 290 to 300. These represent the most desirable red tart cherry sites. The major soils are well drained, moderately coarse textured and have no restricted root zone within 48 inches of the surface. The slopes range ideally from 2 to 12 percent. The elevation above the principal spring freeze line is over 50 feet. Air flow is unimpeded or is blocked only by minor obstructions that can be easily removed. The probability of damaging freeze or cold weather during the time of fruit set is 2 years or less in 10 years. The probability of extreme cold winter temperatures is 2 years or less in 10 years. The soils, physiographic features and micro-climate individually and collectively create few limitations to production.

YELLOW

Areas colored yellow on the map have a range of 225 to 285. They are good tart cherry producers but need intensive management practices to overcome the moderate limitations to production. One to three of the following factors may cause the lowered site rating:

1. Low available water capacity.
2. Low natural fertility.
3. In some locations, a water table within 4 or 5 feet of the surface.
4. Slopes somewhat steeper than 12 percent.
5. Elevations less than 50 feet, but over 20 feet above the principal spring freeze line.

The probability of damaging freeze, cold weather, or fog during blossom time or the probability of extremely low winter temperatures is not more than 3 to 4 years in 10 years.

Other features that may depress the rating are: areas needing random drainage; areas of nearly level land within dish-shaped terrain in which cold air is likely to stagnate; blockages that stop air movement; or small areas that are adversely affected because of very coarse or fine textured soil inclusions. Symbols are used to indicate these features on the map.

RED

Areas colored red have a range from 170 to 220. The severe limitations are difficult to overcome by management. All limitations should be considered carefully before planning to plant these areas to red tart cherries.

Where small areas of this range occur within areas with fewer limitations, it may be feasible to consider corrective measures. One limiting factor of sufficient severity which cannot be corrected will suffice to rate a site between 170 - 220. Adverse characteristics are:

1. Low available water capacity.
2. Low natural fertility.
3. Moderately slow permeability.
4. Slopes that cause difficulty in efficient machinery operation.
5. Elevations near or at the principal spring freeze line with a probability of a freeze of 4 to 5 years in 10 years or extreme low temperature of 4 to 5 years in 10 years.
6. Major obstruction to air flow.

UNCOLORED

Areas having a rating of 165 or below are uncolored on the map. The limitations are so severe that these areas are not considered as red tart cherry sites.

The principal limiting factors are:

1. Poorly drained soils.
2. Extremely droughty, infertile soils.
3. Slopes that are too steep for orchard equipment operation.
4. Large areas having little or no air drainage.
5. Location below the principal spring freeze line with a frequency of 6 or more of 10 years of spring freeze and the same probability of extreme low winter temperatures.
6. Areas subject to frequent occurrence of fog during blossom period.

INTERPRETATION OF THE MAP

In arriving at a fruit site rating, it is assumed that modern soil and orchard management practices are to be applied. Special efforts are made not to be influenced in a site evaluation of a particular parcel by effects of either a substantially higher or lower level of management than is the norm on a producing orchard now occupying such a site. It is realized that improvements in management practices will continue to affect production in the future, but they are not likely to change a site rating.

Modification of Hazards

Available weather data is useful in broad determinations of whether or not certain crops can be considered for an area. The microclimate influences that affect fruit set cannot be obtained from existing weather data.

The site rating was made on the basis of the "natural characteristics" of the site and not for the possibility of using artificial heating for freeze protection. The need for additional microweather information is recognized. Such information would permit refinement in estimating the size of cold air storage basins in relation to drainage areas. The fruit site inventory was developed by today's standards of plant selection for red tart cherry planting stock. It does not rule out the possibility of improved varieties through a plant selection program that may reduce the site requirements of today's planting stock. The use and interpretations of the site map will not eliminate the need for onsite study and investigation for individual tracts.

Colors used on the map indicate the relative degree of hazard that exists for producing red tart cherries. Some of these hazards can be controlled. Also, some sites colored yellow or red may be as productive as the green colored sites if the limiting factors are corrected.

A minor air flow block may be removed by opening up wooded areas or even by removing undergrowth. Small ridges of earth may be flattened with little effort. A major block to air flow such as a large earth obstruction can require major engineering to remove. This may be advisable if the cost-return ratio is favorable.

Areas with favorable air drainage but too steep for orchard operations may be reclaimed by reshaping the slopes. Where steep slopes are remade to more gentle slopes to accommodate mechanized operations, problems of severe erosion, rapid runoff, reduced aeration and unbalanced plant nutrition in the exposed subsoil material can result. Very intensive soil management may be needed to overcome these difficulties.

Sites rated low because of low available water capacity may be made productive with irrigation and intensive fertilization. Small wet spots may be drained, but tile drainage of orchards sometimes require increased maintenance because of clogging by fruit tree roots.

Advantage should be taken of land forms to minimize cold weather damage before introducing artificial heat.

HOW TO USE THE RED TART CHERRY SITE INVENTORY

Locating Areas

At the back of this report is an index map and the red tart cherry site inventory map consisting of many sheets. On the index map are rectangles numbered to correspond to the sheets of the site map so that the map for any area can be located easily. On each map the site boundaries are outlined. Ad hoc symbols appearing within site boundaries are explained in the legend sheet. Small islands of desirable red tart cherry sites may occur in the unmapped area. Generally, they are too small in size to be considered for commercial orchards.

Finding Information

Explanation of colors used, page 5.

Definition of terms used are given in the appendix.

Explanation of symbols given in legend, on back of Index to Maps.

Soil information for Leelanau County is available on request from the Soil Conservation Service Field Office in Lake Leelanau, Michigan.

For selected readings on climate, refer to references given in the appendix.

APPENDIX

To aid understanding and insure uniform interpretation, definitions or explanations are given here for some of the terms used in this report.

Conditions affecting the microclimate of a particular site can increase or decrease the hazard of frost, fog or other localized climate important to the production of fruit or other very sensitive crops. The following is an attempt to define items that must be recognized in evaluating fruit sites. These are things which the experienced grower unconsciously considers when looking at a potential orchard site. By experience these items have been found to influence success or failure of orchards on various sites over many years.

Air Flowageway

This is assumed to be the same flowageway as used by water except that it may be modified by physical conditions that affect air movement but that may not hinder water flow.

Air Movement

The movement of air under calm (no wind) conditions is due to changes in temperatures of the air. Warm air moves upward because it is less dense (lighter) and when moving upward it expands and cools. Cooling causes the air to become more dense, making it descend. This movement by convection is a principle which orchardists attempt to use and manipulate to their advantage. Unlike water, air moving down a slope tends to pile up behind a barrier and may build up to several times the height of the barrier before flowing over it and on downslope. It is suggested that this buildup may be caused by the leading edge being forced upward as it mixes with upward-moving air warmed by radiation from the top of the barrier. Surface drag caused by resistance to air flow over ground vegetation also influences the downward flow of colder air. Observations indicate that movement of air down an air flowageway is not at a steady rate but tends to surge, then slow, then surge ahead again.

Airshed

For this application it can be assumed that the airshed will be the same area as a watershed contributing to a common outlet or storage basin.

Air Storage Over Water

Air flowageways ending over water are more desirable than those ending over land. Water, having better heat conductivity and greater heat storage than soil, warms the incoming cold air in contact with it causing that air to rise, thus making room for more cold air entering from the flowageway.

Coarse Fragments

Rock or mineral particles greater than 2.0 millimeters in diameter.

Fog Damage

This refers to periods of daytime fog that inhibit the pollination of blossoms or that can cause delay in application of sprays for control of diseases. These conditions may occur in small pockets or they may be common to larger areas that are subject to marine influence.

Major Obstruction

A closed barrier or constriction in an air flowageway which will require large expenditures of time and money to correct is considered a major obstruction. Examples are: raised roadbed or buildings constructed across an air flowageway; or large earth ridges or even conifer swamps which slow cold air movement to lower elevations.

Minor Obstruction

A minor obstruction is a constriction of air flowageway which can be readily removed at relatively small cost. Examples are: trees or small earth ridges which impede air movement to lower elevations.

Microclimate

This refers to the climate of an area, usually small, over which weather conditions are substantially the same. Differences of soil, soil cover, elevation and other factors can be responsible for significant variation in microclimate in areas only a few yards to a few hundred feet apart.

Pan

Horizon or layer in soils that is strongly compacted, indurated, or very high in clay content.

Principal Spring Freeze Line

The principal spring freeze line is a locally determined elevation line which separates favorable from unfavorable spring temperatures for red tart cherry production. The frequency or severity of loss decreases with an increase of elevation above the principal spring freeze line.

Soil Drainage

As a natural condition of the soil, soil drainage refers to the conditions of frequency and duration of periods of saturation or partial saturation that existed during the development of the soil.

Spring Damage

This refers to partial or complete kill of fruit due to below freezing temperatures occurring from the time of spring bud swell to 14 to 18 days after bloom. It may also include poor pollination and fruit set because of cloudy days, rain or fog during blossom time.

Storage Basin

The lowest area to which air drains of its own free flow.

Minor Storage Basin

The area in which air may be held until sufficient fill takes place for overspillage to a major basin.

Size of Storage Basin

No definite criteria are available to say how large a storage basin should be for a definite drainage area. The larger the drainage area, the greater the size of the storage basin needed. It should be of sufficient size to permit the storage of cold air until daylight hours and accompanying warming.

Winter Temperature Injury

This refers to injury to fruiting buds and wood caused by temperature extremes or rapid fluctuation.

1. Wood injury associated with immaturity - early winter.
2. Injury associated with drought (long periods of extremely cold air) - midwinter.
3. Injury to wood and bark due to an extremely fast drop in temperature (moderate winter temperature to very frigid temperature) - midwinter.
4. Injuries characteristic of late winter conditions.

Injuries such as trunk splitting that cause major damage to the structure of a tree received a zero rating for red tart cherries.

REFERENCE MATERIAL

Research Report 26 - Farm Science, Michigan Freeze Bulletin, Mich. State Un., Agric. Exp. Sta. 1965

Frost and Prevention of Frost Damage, Floyd D. Young. Farmer's Bulletin No. 1484, 1967 Rev.

World Meteorological Organization - Tech. Note 51 - Protection Against Frost Damage, World Meteorological Organization #133, T.P. 60

Types of Spring Freezes in Michigan - Their Relationship to Protection Equipment, Ceel Van Den Brink, ESSA Weather Bureau, Mich. State Un., East Lansing, Mich. 1968

Research Report 78 - Natural Resources Meteorological Drouth in Michigan, N. D. Strommen, C. Van Den Brink and E. H. Kidder, Mich. State Un., Agric. Exp. Sta., East Lansing, Mich. 1969

The Helicopter Rotor as a Means of Controlling Frost Damage in Fruit Orchards, C. M. Hansen, Reprint from Quarterly Bulletin of Mich. Agric. Exp. Sta., Vol. 34, No. 2, pp. 182-185, Nov. 1951, Mich. State Un.


Proceedings of Air Drainage and Land Forming Workshop for Frost Control on Fruit Sites - Traverse City, Michigan. Compiled by USDA, SCS, 1969

The Local Climate of NES, Hedmark, Dr. K. Utaaker, Dept. of Meteorology, Un. of Bergen, Norway, 1963.


Land Reshaping for Cherry Orchards, Guy E. Springer, Paper presented to ASAE Dec. 17, 1958, Chicago, Ill.

Climate of Michigan by Stations - Michigan Weather Service in cooperation with U.S. Weather Bureau.

The Climate Near the Ground - Rudolf Geiger, University of Munich, Germany, Harvard University Press, Cambridge, Mass. 1965



INDEX TO MAP SHEETS
LEELANAU COUNTY, MICHIGAN



LEELANAU COUNTY, MICHIGAN

CONVENTIONAL SIGNS

WORKS AND STRUCTURES

Highways and roads

Good motor

Poor motor

Highway markers

U. S.

State or county

Railroads

Single track

Bridges and crossings

Road

Railroad

Mine and quarry

Gravel pit

Forest fire or lookout station ...

Lighthouse

Cemetery

Dams

RELIEF

Escarpments

Bedrock

Other

Prominent peak

Depressions

Crossable with tillage implements

Not crossable with tillage implements

Gravel

Stoniness

Rock outcrops

Chert fragments

Clay spot

Sand spot

Gumbo or scabby spot

Severely eroded spot

Blowout, wind erosion

Gully

Borrow pit

Short steep slope

BOUNDARIES

County

Minor civil division

Reservation

Small park, cemetery, airport ...

Land survey division corners ...

DRAINAGE

Streams, double-line

Perennial

Intermittent

Streams, single-line

Perennial

Intermittent

Crossable with tillage implements

Not crossable with tillage implements

Lakes and ponds

Perennial

Intermittent

Spring

Marsh or swamp

Wet spot

Drainage end

AD HOC SYMBOLS

Physiographic features cause lower temperatures during critical blossom period

Concave surface causing slow air movement

Major block to downward air movement

Soils with special limitations

Topographic features with many depressions that collect and hold cold air. Also known as pitted topography or kettles.....

INTERPRETATIONS FOR FRUIT SITE RATING

TOTAL SCORE

MAP COLOR


DIFFICULTY OF OVERCOMING OF LIMITATIONS TO PRODUCTION

300 - 290



SLIGHT

285 - 255




MODERATE

220 - 170




SEVERE

165 OR LESS



VERY SEVERE

Photobase from 1965 aerial photography. Positions of 5,000-foot grid ticks are approximate and based on the Michigan coordinate system, central zone. Land division corners are approximately positioned on this map.




1 Mile
5,000 Feet
Scale 1:20,000
LEELANAU COUNTY,
MICHIGAN NO. 7



1 Mile
5000 Feet
Scale 1:20000
LEELANAU COUNTY,
MICHIGAN NO. 8
(Joins sheet 10) (11)



LEELANAU COUNTY,
MICHIGAN NO. 9



1 310 000 FEET

515 000 FEET

R. 12 W. | R. 11 W.

(Joins sheet 13)


(Joins sheet 8)

530 000 FEET

NORTHPORT


1 320 000 FEET

(Joins sheet 11) T. 31 N.



LEELANAU COUNTY,
MICHIGAN NO. 10

Scale 1:20000



510 000 FEET |

4


1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

Scale 1:20000

(Joining sheet 13)

LEELANAU COUNTY,
MICHIGAN NO. 12

(Joins sheet 15) | (Joins sheet 16)



R. 12 W. | R. 11 W.
515 000 FEET

(Joins sheet 10)



1 Mile
5000 Feet

Scale 1:20000

LEELANAU COUNTY,
MICHIGAN NO. 13




(Joins sheet 12)

(Joins sheet 14)

(Joins sheet 16) | (Joins inset, sheet 14)






LEELANAU COUNTY,
MICHIGAN NO. 15

(Joins sheet 16)

(Joins sheet 12)

(Joins sheet 17)



(Joins sheet 15)

1 1 275 000 FEET

510 000 FEET

(Joins sheet 18)

(204)


(22)

(Joins inset sheet 14)

1 Mile
5000 Feet
0 1000 2000 3000 4000 5000

Scale 1:20000

LEELANAU COUNTY,
MICHIGAN NO. 16





(Joins sheet 16)

R. 12 W. | R. 11 W.

530 000 FEET



1 Mile
5000 Feet

Scale 1:20000

(Joins sheet 19) T. 30 N.

LEELANAU COUNTY,
MICHIGAN NO. 18

LAKE LEELANAU

CHESAPEAKE
AND
OHIO

SUTTONS
BAY

MARYS
BATTERY

LEELANAU

SUTTONS

SUTTONS
BAY

36

24

25

31

30

32

29

33

21


28

27

(Joins sheet 17)


(Joins sheet 24)

510 000 FEET




1:440 000 FEET

1:225 000 FEET



LEELANAU COUNTY,
MICHIGAN NO. 21


(Joins sheet 26)




1 Mile
5000 Feet
Scale 1:20000
LEELANAU COUNTY,
MICHIGAN NO. 22



(Joins sheet 22) T. 29 N.




(29) | (Joins sheet 24)
LEELANAU COUNTY,
MICHIGAN NO. 23
Scale 1:20000



1 Mile
5000 Feet
Scale 1:20000

LEELANAU COUNTY,
MICHIGAN NO. 24



LEELENAU COUNTY,
MICHIGAN NO. 25

(Joins sheet 30) 435 000 FEET

(Joins sheet 26) T. 29 N.

(Joins sheet 20)


R. 15 W. | R. 14 W.

1 415 000 FEET





LEELANAU COUNTY,
MICHIGAN NO. 27






(Joins sheet 23)

R. 12 W.

505 000 FEET

1 240 000 FEET



LEE LANAU COUNTY,
MICHIGAN NO. 28

(Joins sheet 27)

1230 000 FEET

(Joins sheet 29)

T. 29 N.


(Joins sheet 33)

1490 000 FEET



(Joins sheet 28) | (23)

(Joins sheet 24)




LEELANAU COUNTY,
MICHIGAN NO. 29

(Joins sheet 34)


530 000 FEET



LEELANAU COUNTY,
MICHIGAN NO. 30




LEELANAU COUNTY,
MICHIGAN NO. 31





LEELANAU COUNTY,
MICHIGAN NO. 32





LEELANAU COUNTY,
MICHIGAN NO. 34





(Joins sheet 31)

R. 14 W. | R. 13 W.

460 000 FEET

N

1 Mile
5 000 Feet

Scale 1:20000

Joins sheet 37)

LEELANAU COUNTY,
MICHIGAN NO. 36



22

23

24

19

20

72

72

(Joins sheet 35)

27

26

25

30

29

E M P I R E

K A S S O N

1 200 000 FEET

T. 28 N

1/4

1/2

3/4

1/4

1/2

3/4

34

35

36


31

32

BLAND
CEMETERY

440 000 FEET

BENZIE COUNTY



(72)

(Joins sheet 36)

21

22

23

24

19

28

27

26

25

30

(12)

K

A

S

S

O

N

F I F E L A K E S T A T E F O R E S T

33

34

35

36

31

WILSON CEMETERY

EAST KASSON CEMETERY

Bright Lake


Davis Lake

Hart Lake

BENZIE COUNTY

GRAND TRAVERSE COUNTY

LEELANAU COUNTY,
MICHIGAN NO. 37



N

(Joins sheet 33)

R. 12 W.

505 000 FEET



(Joins sheet 37)



1 Mile

5000 Feet

205 000 FEET

28 N.

(Joins sheet 39)

1

5000

4000

3000

2000

1000

0

1/4

1/2

3/4

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306



